


REV.	DESCRIPTION	DRAWN	CHECKED	APPROVED
A	NEW RELEASE	ZQJ 11/18/2014	~	ZQJ 11/18/2014
B	ADD P/N CODE	CJJ 11/18/2014	~	

NOTES:

- MATERIAL
  - Insulator: Thermoplastic(UJL 94V-0)
  - Contact: Copper Alloy
  - Sheet: Steel
- SPECIFICATIONS
  - Storage Temperature: -20~+80°C
  - Insulation Resistance: 1,000MΩ min
  - Dielectric Withstanding Voltage: AC500V Per Minute
- PRODUCT NUMBER CODE:



Dimension

Position	A	B	C	D
09	17.90	24.99	30.80	16.33
15	26.50	33.32	39.14	24.66
25	40.00	47.04	53.04	38.38
37	56.50	63.50	69.32	54.84

GENERAL TOLERANCE	ANGLE TOLERANCE	CUSTOMER
X: ±0.60 X: ±0.38 .XX: ±0.25	X: ±5° X: ±3° .XX: ±2°	

PROJECTION	TITLE
UNITS: mm SHEET SIZE: A4	<b>IPC D-SUB WITH FLAT CABLE</b> LL1050-2B

- Cable Style: 1: TYPE 1
- Length Dim L: 0150: 150mm, 0500: 500mm, 0100: 100mm, 0400: 400mm, 1500: 1500mm
- Wire Diameter: 1.00: 100 folwer mark, 2.00: 127 red mark, 3.00: 100 red mark, 4.00: 127 folwer mark
- Flat Cable Color: As: Gray
- Rivet type: P:W/ Thread(UNC #4-40), N:W/O Thread
- Contact plating: 0: Selective gold flash
- Shell plating: N:Nickel
- Housing color: E:Black, L:Blue
- Connector positions: 09: 9pin, 25: 25pin, 15: 15pin, 37: 37pin

ITEM	PART NAME	PART NO.	MATERIALS	FINISHED	DRAWING NO.
1	HOUSING		COPPER ALLOY	GOLD OR TIN PLATED	
2	CONTACT		THERMOPLASTIC	UL 94 V-0	

慈溪蓝翎电子有限公司  
CIXI LANLING ELECTRONICS CO., LTD.